## Andhra Pradesh State Council of Higher Education

#### **Notations:**

**Highlighter:** 

be always auto saved ):

Is this Group for Examiner?:

1. Options shown in green color and with ✓ icon are correct.

2.Options shown in red color and with \* icon are incorrect.

Auto Save on Console? (SA type of questions will

**Question Paper Name:** Shift2 **Duration:** 180 **Total Marks:** 200 **Display Marks:** No **Calculator:** None **Magnifying Glass Required?:** Nο **Ruler Required?:** No **Eraser Required?:** Nο **Scratch Pad Required?:** No Rough Sketch/Notepad Required?: No **Protractor Required?:** No **Show Watermark on Console?:** Yes No

Yes

No



Mechanical Engineering 19th Sep 2021

Section Id:

477203413

**Section Number:** 

1

**Mandatory or Optional:** 

Mandatory

**Number of Questions:** 

50

**Section Marks:** 

50

**Enable Mark as Answered Mark for Review and** 

Yes

**Clear Response:** 

Question Number: 1 Question Id: 47720321033 Display Question Number: Yes Is Question

Mandatory: No

If  $k \neq -5$  is a real number, then, the number of solutions to the following system of

equations

$$3x - y + 4z = 3$$

$$x + 2y - 3z = -2$$

$$6x + 5y + kz = -3$$
 is

**Options:** 

1. \* 0

2. 🗸 1

3. \* 2

4. \* infinitely many

Question Number: 2 Question Id: 47720321034 Display Question Number: Yes Is Question

Mandatory: No



$$\begin{vmatrix} 1 & 1+p & 1+p+q \\ 2 & 3+2p & 4+3p+2q \\ 3 & 6+3p & 10+6p+3q \end{vmatrix} =$$

- 1. \* 0
- 2. 🗸 1
- 3. \* 2
- 4 **×** 3

Question Number : 3 Question Id : 47720321035 Display Question Number : Yes Is Question Mandatory : No

Let |A| denote the determinant of the matrix A. If A is a square matrix of order 3, and |AA| = r|A|, then the value of r is

### Options:

- 1. \* 0
- 2. \* 4
- 3. \* 16
- 4. 🗸 64

Question Number: 4 Question Id: 47720321036 Display Question Number: Yes Is Question

collegedunia

Mandatory: No

If 
$$\begin{vmatrix} y & y \\ 1 & y \end{vmatrix} = \begin{vmatrix} 3 & 4 \\ 1 & 2 \end{vmatrix}$$
, then the value of y is

- 1. \* 0
- 2. \* 1
- 3. 🗸 2
- 4. **\*** 3

Question Number : 5 Question Id : 47720321037 Display Question Number : Yes Is Question Mandatory : No

Let  $\begin{vmatrix} 2 & 3+i & -1 \\ 3-i & 0 & -1+i \\ -1 & -1-i & 1 \end{vmatrix} = a+ib$ , where a and b are real numbers. Then the value of b is

#### Options:

- 1. 0
- 2 \* 1
- 3. \* 3
- 4. \* 4

Question Number : 6 Question Id : 47720321038 Display Question Number : Yes Is Question Mandatory : No

collegedunia

If 
$$\frac{y^2-5y+1}{(y+1)(y+2)(y+3)} = \frac{a}{y+1} + \frac{b}{(y+1)(y+2)} + \frac{c}{(y+1)(y+2)(y+3)}$$
, then,

$$a = 1, b = 10, c = 25$$

$$a = 1, b = -10, c = 25$$

$$a = 5, b = 10, c = 25$$

$$a = 5, b = -10, c = 25$$

Question Number : 7 Question Id : 47720321039 Display Question Number : Yes Is Question Mandatory : No

$$\frac{2x+3}{(x^2+1)(x+4)} =$$

$$\frac{5}{17(x+4)} + \frac{5x+14}{17(x^2+1)}$$
1. \*\*

$$\frac{-5}{17(x+4)} - \frac{5x+14}{17(x^2+1)}$$

$$\frac{-5}{17(x+4)} + \frac{5x+14}{17(x^2+1)}$$





$$\frac{-5}{17(x+4)} + \frac{5x-14}{17(x^2+1)}$$

4.

Question Number : 8 Question Id : 47720321040 Display Question Number : Yes Is Question Mandatory : No

If x and y are two distinct real numbers, then, the number of values of  $\theta$  in  $[0,2\pi]$  for which cosec  $\theta = \frac{x^2 - y^2}{x^2 + y^2}$  is

#### Options:

- 1. 0
- 2. \* 1
- 3. \* 2

Question Number : 9 Question Id : 47720321041 Display Question Number : Yes Is Question Mandatory : No

If  $\cos(\alpha - \beta) + \cos(\beta - \gamma) + \cos(\gamma - \alpha) = -\frac{3}{2}$ , then  $\cos \alpha + \cos \beta + \cos \gamma = -\frac{3}{2}$ 

- \_ 3 1 \*\*
- <sub>2 ¥</sub> −1
- 3. 🗸 0

4. \* 1

Question Number : 10 Question Id : 47720321042 Display Question Number : Yes Is Question Mandatory : No

For all real numbers  $\theta$ , the value of  $\sin^2\theta + \cos^4\theta$  is greater than or equal to

#### **Options:**

- 1 🗸 4
- 2 × 1
- 3. **\*** 4
- **2**

Question Number : 11 Question Id : 47720321043 Display Question Number : Yes Is Question Mandatory : No

Let x be a real number such that  $tan\left(\frac{\pi}{4} + x\right) + tan\left(\frac{\pi}{4} - x\right) = 2$ . Then x is of the form  $x = n\pi + a$ , where  $n \in \mathbb{Z}$ , and  $a = n\pi + a$ 

- 1.
- $\frac{\pi}{3}$
- $\frac{\pi}{4}$

Question Number : 12 Question Id : 47720321044 Display Question Number : Yes Is Question Mandatory : No

If  $(sin^{-1}x) > (cos^{-1}x)$ , then x belongs to the interval

#### **Options:**

$$[0,\frac{1}{\sqrt{2}})$$

$$(\frac{1}{\sqrt{2}}, 1]$$

$$\left[\frac{1}{\sqrt{2}},1\right]$$

$$\left[0,\frac{1}{\sqrt{2}}\right]$$

Question Number : 13 Question Id : 47720321045 Display Question Number : Yes Is Question Mandatory : No

Consider a triangle  $\triangle ABC$ , with sides of length a,b and c, and angles A,B and C. If a,b,c and the area of the triangle  $\triangle ABC$  are all rational, then

$$\tan \frac{B}{2}$$
 is rational and  $\tan \frac{C}{2}$  is irrational.

$$\tan \frac{B}{2}$$
 is irrational and  $\tan \frac{C}{2}$  is rational.

$$\tan \frac{B}{2}$$
 and  $\tan \frac{C}{2}$  are both rational.

$$\tan \frac{B}{2}$$
 and  $\tan \frac{C}{2}$  are both irrational.

4. \$

Question Number : 14 Question Id : 47720321046 Display Question Number : Yes Is Question Mandatory : No

Consider a triangle  $\triangle ABC$ , with sides of length a,b and c, and angles A,B and C. If 3a=b+c, then the value of  $\cot \frac{B}{2} \cdot \cot \frac{C}{2}$  is

**Options:** 

- 1. \* 0
- 2. \* 2
- 3. **\***  $\sqrt{3}$
- <sub>1</sub> 2

Question Number : 15 Question Id : 47720321047 Display Question Number : Yes Is Question Mandatory : No

$$2 \tan^{-1} \left( \frac{3}{4} \right) - \tan^{-1} \left( \frac{17}{31} \right) =$$



$$\frac{\pi}{4}$$

$$\frac{\pi}{2}$$

# Question Number : 16 Question Id : 47720321048 Display Question Number : Yes Is Question Mandatory : No

Consider a triangle  $\triangle ABC$  with angles A,B and C. If  $\cos A + \cos B + \cos C = \frac{3}{2}$ , then the triangle  $\triangle ABC$  is

#### Options:

isosceles, with one of the angles equal to 
$$\frac{\pi}{6}$$
.

## Question Number : 17 Question Id : 47720321049 Display Question Number : Yes Is Question Mandatory : No

The value of 
$$\cos^2 x + \cos^2 \left(x + \frac{\pi}{3}\right) + \cos^2 \left(x - \frac{\pi}{3}\right)$$
 is



1. \* 1

$$\frac{3}{2}$$

Question Number : 18 Question Id : 47720321050 Display Question Number : Yes Is Question Mandatory : No

The value of 
$$\left(\frac{\sqrt{3}+i}{\sqrt{3}-i}\right)^3$$
 is

### Options:

Question Number : 19 Question Id : 47720321051 Display Question Number : Yes Is Question Mandatory : No

If 
$$x + iy = \frac{a+ib}{a-ib}$$
, then  $x^2 + y^2 =$ 



- 1 %
- 2. 🗸 1
- 3. \* 2
- 4. \*\* 4

Question Number : 20 Question Id : 47720321052 Display Question Number : Yes Is Question Mandatory : No

If a circle of radius 5 touches the circle  $x^2 + y^2 - 2x - 4y = 20$  at the point (5,5), then, its center is

## Options:

- 1. \* (8,8)
- 2. \* (8,9)
- 3. 🗸 (9,8)
- 4. \* (9,9)

Question Number : 21 Question Id : 47720321053 Display Question Number : Yes Is Question Mandatory : No

The equation  $9x^2 - 24xy + 16y^2 - 20x - 15y = 60$  represents



Question Number : 22 Question Id : 47720321054 Display Question Number : Yes Is Question Mandatory : No

Let  $(x_j, y_j)$ , j=1,2,3,4, be points of intersection of the parabola  $y^2=4ax$  and the circle  $x^2+y^2+2gx+2fy+c=0$ .

Then 
$$y_1 + y_2 + y_3 + y_4 =$$

Options:

$$-\frac{1}{2}$$

Question Number : 23 Question Id : 47720321055 Display Question Number : Yes Is Question Mandatory : No

The length of the major axis of the ellipse  $9x^2 + 5y^2 - 30y = 0$  is



Question Number : 24 Question Id : 47720321056 Display Question Number : Yes Is Question Mandatory : No

If S (-1, 1) is one of the foci of a hyperbola, x - y + 3 = 0 is its directrix corresponding to S and 3 is its eccentricity, then, the equation of the hyperbola is

#### Options:

$$7x^2 + 18xy + 7y^2 + 50x + 50y + 77 = 0$$

$$7x^2 + 18xy + 7y^2 + 50x - 50y + 77 = 0$$

$$7x^2 - 18xy + 7y^2 + 50x - 50y + 77 = 0$$

$$7x^2 - 18xy - 7y^2 - 50x + 50y + 77 = 0$$



Question Number : 25 Question Id : 47720321057 Display Question Number : Yes Is Question Mandatory : No

The equation  $4(x - 2y + 1)^2 + 9(2x + y + 2)^2 = 25$  represents

### Options:

- 1. \* a parabola
- an ellipse 2. ✔
- a hyperbola
- 4. \* a circle

Question Number : 26 Question Id : 47720321058 Display Question Number : Yes Is Question

Mandatory: No

Let f be a twice differentiable function such that f''(x) + f(x) = 0, and f'(x) = g(x). If  $h(x) = [f(x)]^2 + [g(x)]^2$ , and h(10) = 20, then h(40) = 1

## Options:

- 1. 🗸 20
- 2. \* 40
- 3. \* 80
- 4. \* 160



Question Number : 27 Question Id : 47720321059 Display Question Number : Yes Is Question

Mandatory: No

$$\lim_{x \to \frac{\pi}{2}} \left( \frac{\cot x - \cos x}{\cos^2 x} \right) =$$

$$4. \approx \frac{\pi}{2}$$

Question Number : 28 Question Id : 47720321060 Display Question Number : Yes Is Question Mandatory : No

Let  $\mathbb{R}$  be the set of all real numbers. Let  $f: \mathbb{R} \to \mathbb{R}$  satisfy the condition:

 $|f(x)-f(y)| \le |x-y|^{2021}$ , for all  $x,y \in \mathbb{R}$ . Then the value of f'(2022) is



The number of real roots of the equation  $x + e^x = 0$  is

### Options:

- 1. \* 0
- 2. 🗸 1
- 2 \*\*
- Infinitely many

Question Number : 30 Question Id : 47720321062 Display Question Number : Yes Is Question Mandatory : No

If 
$$y = \operatorname{Tan}^{-1}\left(\frac{\sqrt{1+\sin x} + \sqrt{1-\sin x}}{\sqrt{1+\sin x} - \sqrt{1-\sin x}}\right)$$
, then  $\frac{dy}{dx} = \frac{1}{2}$ 

$$\cot^2 x$$

- 1. 🕷
- sec<sup>2</sup> *x*
- $-\frac{1}{2}$



Question Number : 31 Question Id : 47720321063 Display Question Number : Yes Is Question

Mandatory: No

The equation of the tangent to the curve  $x=\sin 3t$ ,  $y=\cos 2t$ , at  $t=\frac{\pi}{4}$  is given by

Options:

$$\sqrt{2}x - 3y - 2 = 0$$

1. 3

$$\sqrt{2} x + 3y - 2 = 0$$

$$2\sqrt{2} x - 3y - 2 = 0$$

$$2\sqrt{2} x - 3y + 2 = 0$$

Question Number : 32 Question Id : 47720321064 Display Question Number : Yes Is Question Mandatory : No

An open tank with a square base (with side x) and vertical sides (with height y) is to be constructed from a metal sheet so as to hold a given quantity of water. The cost of the material will be the least if



$$4x=y$$

Question Number : 33 Question Id : 47720321065 Display Question Number : Yes Is Question Mandatory : No

The function  $f(x) = x^3 - 12x^2 + 36x + 48$ , is decreasing in the interval

#### **Options:**

Question Number : 34 Question Id : 47720321066 Display Question Number : Yes Is Question Mandatory : No

A shopkeeper can buy x items for Rs.  $\left(\frac{x}{5} + 500\right)$ . He can sell the x items at the rate Rs.  $\left(5 - \frac{x}{100}\right)$  per item. Then the number of items he should sell to make maximum profit is

4. \* 500

Question Number : 35 Question Id : 47720321067 Display Question Number : Yes Is Question Mandatory : No

If 
$$z = ax^2 + 2hxy + by^2$$
, then  $x \frac{\partial z}{\partial x} + y \frac{\partial z}{\partial y} =$ 

Options:

- 1. \*\*
- 2. **\*** z<sup>2</sup>
- 3. \*  $\frac{1}{2}Z$
- 4. **✓** 2z

Question Number : 36 Question Id : 47720321068 Display Question Number : Yes Is Question Mandatory : No

$$\int_{-1}^{1} \frac{x \sin^{-1} x}{\sqrt{1-x^2}} \ dx =$$

- 1 🚜
- 2. \* 1

Question Number : 37 Question Id : 47720321069 Display Question Number : Yes Is Question Mandatory : No

The area of the region bounded by the curve  $y = x^2 + 4$ , the x-axis and the ordinates at x=1 and x=5 is

Options:

Question Number : 38 Question Id : 47720321070 Display Question Number : Yes Is Question Mandatory : No

$$\lim_{n\to\infty} \sum_{k=0}^{n-1} \, \frac{1}{\sqrt{n^2-k^2}} =$$



Question Number : 39 Question Id : 47720321071 Display Question Number : Yes Is Question Mandatory : No

$$\int_0^1 \frac{2x}{1+x^2} \ dx =$$

Options:

Question Number : 40 Question Id : 47720321072 Display Question Number : Yes Is Question Mandatory : No

$$\int \frac{e^{ax} - e^{-ax}}{e^{ax} + e^{-ax}} dx =$$



(In the following, c is a constant.)

$$\frac{1}{a}\log|e^{ax} + e^{-ax}| + c$$

$$\frac{1}{a} \log |e^{ax} - e^{-ax}| + c$$

$$\frac{1}{2a} \log |e^{ax} + e^{-ax}| + c$$

$$\frac{1}{2a}\log|e^{ax} - e^{-ax}| + c$$

Question Number : 41 Question Id : 47720321073 Display Question Number : Yes Is Question Mandatory : No

$$\int_0^\pi \frac{e^{\cos x}}{e^{\cos x} + e^{-\cos x}} \, dx =$$

Options:

$$\frac{\pi}{2}$$



Question Number : 42 Question Id : 47720321074 Display Question Number : Yes Is Question Mandatory : No

$$\int_{-\pi}^{\pi} \sin^5 x \, dx =$$

- 1. 🗸 0
- $\frac{\pi}{2}$
- 3 \*\* π
- 2π

Question Number : 43 Question Id : 47720321075 Display Question Number : Yes Is Question Mandatory : No

The area of the region bounded by y=|x+3|, the x-axis and the lines x=-6 and x=0 is

- 3 square units
- 9 square units
- 12 square units 3. \*
- 18 square units



The degree of the differential equation  $7x\left(\frac{dy}{dx}\right)^2 - \frac{d^2y}{dx^2} + 10y = \log x$  is

### Options:

- 1. 🗸 1
- 2. \* 2
- 2 **%**
- 4. \* 4

## Question Number : 45 Question Id : 47720321077 Display Question Number : Yes Is Question Mandatory : No

The solution of the differential equation  $\frac{dy}{dx} = y \tan x$ , given that y=1 when x=0, is given by

- $y = \cos x$
- $y = \cos 2x$
- $y = \sec x$
- $y = \sec 2x$



Question Number: 46 Question Id: 47720321078 Display Question Number: Yes Is Question

Mandatory: No

The solution to the differential equation  $(3x^2 + y)\frac{dx}{dy} = x$ , (x > 0), such that y=1 if x=1 is

Options:

$$y = 2x^2 - x$$

$$y = 3x^2 - 2x$$

$$y = 4x^2 - 3x$$

$$y = 5x^2 - 4x$$

Question Number : 47 Question Id : 47720321079 Display Question Number : Yes Is Question Mandatory : No

The differential equation of the family of parabolas having vertex at the origin and axis along the positive y-axis is

$$xy'=2$$

$$2. \checkmark xy' = 2y$$

$$xy' = -2y$$

$$xy' = 2y^2$$



The solution of the differential equation  $\frac{dy}{dx} + y \cot x = 4x \csc x$ ,  $(x \neq 0)$ , given that y=0 when  $x = \frac{\pi}{2}$  is

#### **Options:**

$$y \csc x = x^2 - \frac{\pi^2}{4}$$

$$y \csc x = 2x^2 - \frac{\pi^2}{2}$$

$$y \sin x = x^2 - \frac{\pi^2}{4}$$

$$y\sin x = 2x^2 - \frac{\pi^2}{2}$$

## Question Number: 49 Question Id: 47720321081 Display Question Number: Yes Is Question Mandatory: No

The general solution of the differential equation  $log_e\left(\frac{dy}{dx}\right) = ax + by$  is given by

### **Options:**

$$ae^{ax} + be^{-by} + C = 0$$

1. \*\*

$$ae^{ax} - be^{-by} + C = 0$$

$$\frac{1}{a}e^{ax} + \frac{1}{b}e^{-by} + C = 0$$
3.

$$\frac{1}{a}e^{ax} - \frac{1}{b}e^{-by} + C = 0$$

Question Number : 50 Question Id : 47720321082 Display Question Number : Yes Is Question Mandatory : No

The particular integral of the differential equation  $(D^2 + D - 2)y = \sin x$  is given by

#### **Options:**

$$-\frac{1}{10}\left(\cos x + \sin x\right)$$

$$-\frac{1}{10}\left(\cos x + 3\sin x\right)$$

$$-\frac{1}{10}\left(\cos 3x + \sin 3x\right)$$

$$-\frac{1}{10} (3 \cos x + \sin x)$$

## **Physics**

**Section Id:** 477203414

Section Number: 2

Mandatory or Optional: Mandatory

Number of Questions: 25

Section Marks: 25

**Enable Mark as Answered Mark for Review and** Yes



#### **Clear Response:**

Question Number: 51 Question Id: 47720321083 Display Question Number: Yes Is Question

Mandatory: No

The dimensional formula for gravitational constant, G is

#### **Options:**

- 1.  $\times$  M<sup>1</sup>L<sup>3</sup>T<sup>-2</sup>
- 2.  $\checkmark$  M<sup>-1</sup>L<sup>3</sup>T<sup>-2</sup>
- 3.  $^{*}$   $M^0L^3T^{-2}$
- 4. \*  $M^2L^3T^{-2}$

Question Number : 52 Question Id : 47720321084 Display Question Number : Yes Is Question Mandatory : No

Which of the following quantities have not been expressed in proper units?

- electric field = Newton/Coulomb
- 2. \* surface tension = Newton/meter
- 3. ✓ energy = kg m/s
- 4. \* pressure = Newton/m<sup>2</sup>



Question Number : 53 Question Id : 47720321085 Display Question Number : Yes Is Question

Mandatory: No

A vector A is along positive x-axis. If B is another vector such that AxB is zero, then B could be

Options:

$$3. \times -(\hat{\imath}+\hat{\jmath})$$

4. \* 
$$(\hat{j} + \hat{k})$$

Question Number : 54 Question Id : 47720321086 Display Question Number : Yes Is Question

Mandatory : No

The scalar product of two vectors is  $2\sqrt{3}$  and the magnitude of their vector product is 2.

The angle between them is



The work done by a force is defined as W=F.S. In a certain situation F and S are not zero but the work done is zero when

#### Options:

- F and S are in the same direction
- F and S are in opposite direction
- F and S are at right angles
  3. ✓
- F and S are at 45°

Question Number : 56 Question Id : 47720321088 Display Question Number : Yes Is Question Mandatory : No

A body starts from rest and travels a distance x in first two seconds and a distance y in next two seconds. The relation between x and y is

$$y = 3x$$



A projectile is projected with initial velocity  $(6\hat{\imath} + 8\hat{\jmath})$  m/s. If g = 10 m/s<sup>2</sup> then horizontal range is

#### **Options:**

- 1. \* 4.8 m
- 9.6 m
- 19.2 m
- 4. **\*** 14.0 m

## Question Number : 58 Question Id : 47720321090 Display Question Number : Yes Is Question Mandatory : No

The maximum range of a projectile fired with some initial velocity is found to be 1000 m/s, in the absence of wind and air resistance. The maximum height reached by this projectile is

- 1. ✓ 250 m
- 2. **\*** 500 m
- 1000 m
- 4. **×** 2000 m



The force of friction between two bodies is

#### **Options:**

- 1. parallel to the contact surface
- perpendicular to the contact surface
- inclined at 300 to the contact surface
- inclined at 600 to the contact surface

# Question Number : 60 Question Id : 47720321092 Display Question Number : Yes Is Question Mandatory : No

A body is sliding down an inclined plane under its own weight at constant speed. If the inclination of the plane to the horizontal is 30°, the angle of friction is



Question Number : 61 Question Id : 47720321093 Display Question Number : Yes Is Question

Mandatory : No

A block of mass 5 kg is resting on a smooth surface. At what angle, a force of 20 N be acted on the body so that it will acquire a kinetic energy of 40 J after moving 4m

Options:

- 1. \* 300
- 2. **\*** 45<sup>0</sup>
- 3. **•** 60<sup>0</sup>
- 4. **\*** 120<sup>0</sup>

Question Number : 62 Question Id : 47720321094 Display Question Number : Yes Is Question Mandatory : No

Two men with the weights in the ratio 4:3 run up a staircase in time, in the ratio 12:11. The ratio of power of the first to that of second is

- 1 \* 3
- 2. \* 11
- 3. \* 48

Question Number : 63 Question Id : 47720321095 Display Question Number : Yes Is Question

Mandatory: No

Energy harnessed from flowing water is called-----energy

#### Options:

- Solar
- 2. ✓ Hydel
- 3. \* Tidal
- 4. \* Geothermal

Question Number : 64 Question Id : 47720321096 Display Question Number : Yes Is Question Mandatory : No

The total mechanical energy of a spring-mass system in simple harmonic motion is  $E = 0.5 \text{ m}\omega^2 A^2$ . If the oscillating particle is replaced by another particle of double the mass while the amplitude A remains the same. The new mechanical energy is

- 1. × 2E
- 2. ₩ 0.5 E
- 3. **×** √2 E
- 4. 🗸 E

## Question Number : 65 Question Id : 47720321097 Display Question Number : Yes Is Question Mandatory : No

Sound of frequency 1000 Hz from a stationary source is reflected from an object approaching the source at 30 m/s back to a stationary observer located at the source. The speed of sound in air is 330 m/s. The frequency of the sound heard by the observer is

#### Options:

- 1200 Hz
- 2. \* 1000 Hz
- 3. **\*** 1090 Hz
- 4. \* 1100 Hz

## Question Number : 66 Question Id : 47720321098 Display Question Number : Yes Is Question Mandatory : No

The frequency of a pendulum if it is taken from the earth's surface to deep into a mine

- increases
- decreases
- first increases then decreases



## Question Number : 67 Question Id : 47720321099 Display Question Number : Yes Is Question Mandatory : No

Two waves of lengths 50 cm and 51 cm produced 12 beats per second. The velocity of sound is

#### Options:

- 340 m/s
- 2. 331 m/s
- 3. ✓ 306 m/s
- 4. × 360 m/s

## Question Number : 68 Question Id : 47720321100 Display Question Number : Yes Is Question Mandatory : No

According to reverberation time the final intensity is around

- one-hundredth of the initial intensity
- one-tenth of the initial intensity 2. \*\*
- one-thousandth of the initial intensity
- one-millionth of the initial intensity



## Question Number : 69 Question Id : 47720321101 Display Question Number : Yes Is Question Mandatory : No

An ideal gas has volume V at pressure P and temperature T. Mass of each molecule is m. The density of the gas is

#### Options:

$$4. \checkmark \frac{Pm}{KT}$$

## Question Number : 70 Question Id : 47720321102 Display Question Number : Yes Is Question Mandatory : No

Work done by 0.1 mole of a gas at 27°C to double its volume at constant pressure is (R=2 cal/mol/K)



Question Number: 71 Question Id: 47720321103 Display Question Number: Yes Is Question

Mandatory: No

If the pressure of a gas contained in a closed vessel is increased by 0.4%, when heated by 1°C, its initial temperature is

#### **Options:**

Question Number : 72 Question Id : 47720321104 Display Question Number : Yes Is Question Mandatory : No

A monoatomic ideal gas, initially at temperature  $T_1$  is enclosed in a cylinder fitted with a frictionless piston. The gas is allowed to expand adiabatically to a temperature  $T_2$  by releasing the piston suddenly. If  $L_1$  and  $L_2$  are the lengths of the gas column, before and after expansion respectively,  $T_1/T_2$  is given by

1. \* 
$$\left(\frac{L_1}{L_2}\right)^{2/3}$$

$$2. \checkmark \left(\frac{L_2}{L_1}\right)^{2/3}$$



3. **\*** 
$$\frac{L_1}{L_2}$$

$$L_{2}$$
 $L_{1}$ 

## Question Number : 73 Question Id : 47720321105 Display Question Number : Yes Is Question Mandatory : No

A Carnot's engine operates with source at 127°C and sink at 27°C. If the source supplies 40 kJ of heat energy, the work done by the engine is

#### Options:

## Question Number : 74 Question Id : 47720321106 Display Question Number : Yes Is Question Mandatory : No

The optical fibre consisting of a central core is cladded by material of

#### Options:

slightly lower refractive index





equal refractive index

3. \*

very high refractive index

4. \*

Question Number : 75 Question Id : 47720321107 Display Question Number : Yes Is Question

Mandatory: No

The susceptibility of the superconductor is

#### **Options:**

positive and small

negative and small

positive and unity

and unity negative and unity

### Chemistry

**Section Id:** 477203415

Section Number: 3

Mandatory or Optional : Mandatory

Number of Questions: 25

Section Marks: 25



#### **Clear Response:**

Question Number : 76 Question Id : 47720321108 Display Question Number : Yes Is Question

Mandatory: No

The nucleus of tritium consists of -----

#### Options:

1 proton + 1 neutron

1 proton + 3 neutrons

3. \* 1 proton + zero neutron

4. 1 proton + 2 neutrons

Question Number : 77 Question Id : 47720321109 Display Question Number : Yes Is Question Mandatory : No

Which of the following electronic configuration is not possible?

$$2. \checkmark 1s^2 2s^2 2p^7$$

4. \* 
$$1s^2 2s^2 2p^5$$

Question Number : 78 Question Id : 47720321110 Display Question Number : Yes Is Question Mandatory : No

Radius of 3<sup>rd</sup> Bohr orbit of hydrogen atom is -----

#### Options:

- 6.529A<sup>0</sup>
- 2. **✓** 4.761A<sup>0</sup>
- 2.116A<sup>0</sup>
- 4. **8**.464A<sup>0</sup>

Question Number : 79 Question Id : 47720321111 Display Question Number : Yes Is Question Mandatory : No

Covalent compounds are generally soluble in ------

#### Options:

- 1. ✓ Non-polar solvents
- Polar solvents
- 3. \* Concentrated acids



4. \* All solvents

## Question Number: 80 Question Id: 47720321112 Display Question Number: Yes Is Question Mandatory: No Six electrons are mutually shared in -----**Options:** 1 × F<sub>2</sub> 2. \* Cl<sub>2</sub> 3. \* O2 4. V N2 Question Number: 81 Question Id: 47720321113 Display Question Number: Yes Is Question Mandatory: No To half the molarity of a solution, the following should be adopted. **Options:** Weight of the solute to be doubled Weight of the solvent to be doubled

collegedunia

3. \* Volume of the solvent to be doubled

Volume of the solution to be doubled

Question Number: 82 Question Id: 47720321114 Display Question Number: Yes Is Question

Mandatory: No

The molecular weight of KMnO<sub>4</sub> is "M". In a reaction KMnO<sub>4</sub> is reduced to K<sub>2</sub>MnO<sub>4</sub>. The equivalent weight of KMnO<sub>4</sub> is

Options:

- 1. 🗸 M
- 2. **\*** M/2
- 3. **\*** M/3
- 4. **×** M/4

Question Number : 83 Question Id : 47720321115 Display Question Number : Yes Is Question Mandatory : No

Calculate the weight of NaOH present in 500 ml of 0.5 N Solution

Options:

- 1. \* <sup>5 g</sup>
- 2. **✓** 10 g
- 3. × 12 g
- 4. **\*** 15 g

Question Number : 84 Question Id : 47720321116 Display Question Number : Yes Is Question

**Mandatory: No** 




On addition of NaOH to water
Options:
Ionic product will increase  1. **
2. ** Ionic product will decrease
3. ✓ No change in ionic product of water
H <sub>3</sub> O <sup>+</sup> concentration increases 4.   ■
Question Number : 85 Question Id : 47720321117 Display Question Number : Yes Is Question Mandatory : No
Which of the following is not a buffer solution?
Options:
(CH <sub>3</sub> COOH/CH <sub>3</sub> COONa)
2.  ✓ (HCl/NaCl)
3. * (HCOOH/HCOONa)

4. \* (NH4OH/NH4Cl)

Question Number : 86 Question Id : 47720321118 Display Question Number : Yes Is Question Mandatory : No





In electrolysis of dilute H<sub>2</sub>SO<sub>4</sub>, which of the following is liberated at anode in presence of inert electrode?

collegedunia [India's largest Student Review Platform

#### Options:

- 1. × H2
- 2. SO<sub>2</sub>
- 3. **✓** O<sub>2</sub>
- 4. SO<sub>3</sub>

Question Number : 89 Question Id : 47720321121 Display Question Number : Yes Is Question Mandatory : No

The EMF of the cell Ni/Ni $^{2+}$  (0.01M)/Cl $^{2}$  (0.01M)/Cl $^{2}$ , Pt is ---V if the SRP of nickel and chlorine electrodes are -0.25V and +1.36V respectively

#### Options:

Question Number : 90 Question Id : 47720321122 Display Question Number : Yes Is Question Mandatory : No

Which of the following is correct relation used to measures the hardness of water?



#### **Options:**

$$1 \text{ mg/L} = 1 \text{ ppm} = 0.07^{\circ}\text{Cl} = 0.1^{\circ}\text{Fr}$$

$$1 \text{ mg/L} = 0.1 \text{ ppm} = 0.7^{\circ}\text{Cl} = 0.1^{\circ}\text{Fr}$$

$$1 \text{ mg/L} = 1 \text{ ppm} = 0.7^{\circ}\text{Cl} = 0.01^{\circ}\text{Fr}$$

$$1 \text{ mg/L} = 1 \text{ ppm} = 0.7^{0}\text{Cl} = 1^{0}\text{Fr}$$

Question Number : 91 Question Id : 47720321123 Display Question Number : Yes Is Question Mandatory : No

Which of the following is used as effective coagulant in the municipal water treatment to remove fine suspended and colloidal impurities?

#### **Options:**

Question Number : 92 Question Id : 47720321124 Display Question Number : Yes Is Question Mandatory : No

The general chemical formula of zeolite is



#### **Options:**

- 1. ✓ Na<sub>2</sub>O .Al<sub>2</sub>O<sub>3</sub> .x SiO<sub>2</sub> .y H<sub>2</sub>O
- Al<sub>2</sub>O<sub>3</sub>.H<sub>2</sub>O
- CaSO<sub>4</sub>.2H<sub>2</sub>O
- MgSO4.5H<sub>2</sub>O

Question Number : 93 Question Id : 47720321125 Display Question Number : Yes Is Question Mandatory : No

---- is resulted when electrochemical corrosion happened in acidic environment.

#### **Options:**

Evolution of oxygen

- 1. 🗱
- 2. \* Absorption of oxygen
- Evolution of hydrogen
- Absorption of hydrogen

Question Number : 94 Question Id : 47720321126 Display Question Number : Yes Is Question

Mandatory : No

Impure metal corrodes faster than pure metal due to



Options:
1. ✓ Heterogeneity
2. ** Homogeneity
3. Non-galvanic cell
4. * localize corrosion
Question Number : 95 Question Id : 47720321127 Display Question Number : Yes Is Question
Mandatory : No
The number of repeating units in a polymer is called
Options:
1. * Functionality
2. * Tacticity
3.  ✓ degree of polymerization
Specificity 4. **
Question Number : 96 Question Id : 47720321128 Display Question Number : Yes Is Question
Mandatory : No
The process of vulcanisation makes rubber
Options:

collegedunia India's largest Student Review Platform

1. * Soft
2.  ✓ Hard
3. * Elastic
4. * Swells oils
Question Number : 97 Question Id : 47720321129 Display Question Number : Yes Is Question
Mandatory : No
Which of the following is thermosetting plastic
Options:
1. * PVC
2. * Polystyrene
3. * Teflon
4. Bakelite
Question Number: 98 Question Id: 47720321130 Display Question Number: Yes Is Question
Mandatory : No
The boiling range of petrol fraction is found to be
Options:
1. * 120°C-180°C



- 250°C-320°C
- 3. ✓ 40<sup>0</sup>C-120<sup>0</sup>C
- 4. \* 180°C-250°C

Question Number : 99 Question Id : 47720321131 Display Question Number : Yes Is Question Mandatory : No

Which of the following is not a common component of photochemical smog?

#### **Options:**

- 1. Ozone
- 2. \* Acrolein
- 3. \* Peroxyacetyl nitrate
- 4. Chlorofluorocarbons

Question Number: 100 Question Id: 47720321132 Display Question Number: Yes Is Question

Mandatory: No

White lung cancer is caused by

- 1. \* Asbestos
- 2. V Textiles



- 3. \* Paper
- 4. Silica

### **Mechanical Engineering**

**Section Id:** 477203416

Section Number: 4

Mandatory or Optional: Mandatory

Number of Questions: 100

Section Marks: 100

**Enable Mark as Answered Mark for Review and** 

Yes

**Clear Response:** 

Question Number: 101 Question Id: 47720321133 Display Question Number: Yes Is Question

Mandatory: No

The hacksaw blade using in hand sawing operation removes the material in \_\_\_\_\_\_

#### Options:

Forward stroke

- 1. 🗸
- Reverse stroke
- Expansion stroke
- Backward stroke



Question Number : 102 Question Id : 47720321134 Display Question Number : Yes Is Question
Mandatory : No
Which of the following post processes are required for the cutting edge of the chisel?
Options:
1. * Hardening only
2. * Tempering only
Both hardening and tempering 3. ✓
Carburising 4. **
Question Number : 103 Question Id : 47720321135 Display Question Number : Yes Is Question Mandatory : No
Which of the following is internationally accepted and recognized unit system?
Options:
FPS
2. <b>V</b> SI
3. * MKS

4. \* CGS



Question Number: 104 Question Id: 47720321136 Display Question Number: Yes Is Question Mandatory: No
What is the approximate size of slip gauges?
Options:  40 mm long and 20 mm wide  1. **
2. * 30 mm long and 15 mm wide
3. * 25 mm long and 10 mm wide
4. ✓ 30 mm long and 10 mm wide
Question Number : 105 Question Id : 47720321137 Display Question Number : Yes Is Question Mandatory : No
Which of the following is not a drilling machine related operation?
Options:
Counter sinking  1. **
Counter boring 2. **
3. ✓ Knurling
4. ** Centre drilling

collegedunia

Question Number : 106 Question Id : 47720321138 Display Question Number : Yes Is Question
Mandatory : No
What is the function of chasing dial in centre lathe?
Options:
To pick up the thread accurately at the begging of each cut  1. ✓
To perform taper turning 2. **
To perform knurling  3. **
To perform facing
Question Number : 107 Question Id : 47720321139 Display Question Number : Yes Is Question Mandatory : No
Which of the following operation cannot be performed on Lathe?
Options:
Drilling a hole along the axis of the workpiece  1. **
Drilling a hole perpendicular to the axis of the workpiece 2. ✓
External tapering on the workpiece  3. **
External thread cutting on the workpiece 4. **

collegedunia India's largest Student Review Platform

Question Number : 108 Question Id : 47720321140 Display Question Number : Yes Is Questio	on
Mandatory : No	

For performing single start threading operation on centre lathe, the rake angle of the single point cutting tool should be \_\_\_\_\_?

#### **Options:**

- 1 × 5°
- 2 × 10°
- 3. × 8°
- 4. **✓** 0°

## Question Number : 109 Question Id : 47720321141 Display Question Number : Yes Is Question Mandatory : No

Which of the following is true with respect to Honing operation?

#### **Options:**

- Rotary motion is given to workpiece and tool is stationary
- Tool and workpiece rotate in opposite direction
- Workpiece is stationary and the tool is rotating and reciprocating

Tool and workpiece rotate in the same direction

4. \*\*



Question Number : 110 Question Id : 47720321142 Display Question Number : Yes Is Question
Mandatory : No
Which of the following machining processes does not use multipoint cutting tools?
Options:
1. * Milling
2. * Drilling
Grinding 3. **
4. ✓ Forging
Question Number : 111 Question Id : 47720321143 Display Question Number : Yes Is Question Mandatory : No
In planing operation, the cutting motion is given to and the feed motion is given to
Options:
Workpiece, tool 1. ✓
Tool, workpiece 2. **
3. ** Tool, tool
4. * Workpiece, workpiece



Mandaton, No
Mandatory : No
G01 is the computer numerical controlled machine code for
Options :
Circular interpolation clockwise direction
Circular interpolation counter clockwise direction
2. **
Linear interpolation
3.
Staring the enindle
Staring the spindle 4. **
Question Number : 113 Question Id : 47720321145 Display Question Number : Yes Is Questio Mandatory : No
In computer numerically controlled turning machine tools, the unit for feed is
In computer numerically controlled turning machine tools, the unit for feed is
Options :
Options:  Degrees/millimetres
Options:  Degrees/millimetres  1. **
Options:  Degrees/millimetres  Millimetres/revolution
Options:  Degrees/millimetres   Millimetres/revolution
Options:  Degrees/millimetres  Millimetres/revolution  Revolution/millimetres
Options:  Degrees/millimetres  Millimetres/revolution  Revolution/millimetres
Options:  Degrees/millimetres  Millimetres/revolution  Revolution/millimetres



Question Number : 114 Question Id : 47720321146 Display Question Number : Yes Is Qu	estion
Mandatory : No	
Which of the following welding process does not use consumable electrode for joining two plates?	
Options :	
Submerged arc welding  1. **	
Manual metal arc welding	
Tungsten inert gas welding 3. ✓	
4. * Metal inert gas welding	
Question Number : 115 Question Id : 47720321147 Display Question Number : Yes Is Qu Mandatory : No	estion
	estion
Mandatory : No	estion
Mandatory: No  Which of the following welding process is generally used to weld plastic materials?	estion
Mandatory: No  Which of the following welding process is generally used to weld plastic materials?  Options:	estion
Mandatory: No  Which of the following welding process is generally used to weld plastic materials?  Options:  Ultrasonic welding  Tungsten inert gas welding	estion
Mandatory: No  Which of the following welding process is generally used to weld plastic materials?  Options:  Ultrasonic welding  Tungsten inert gas welding  Manual metal arc welding	estion

collegedunia India's largest Student Review Platform

Mandatory : No
Edge preparation is not required in welding process if the thickness of the plates to be joined is less than
Options :
1. ** 10 mm
2. <b>✓</b> 5 mm
3. * 15 mm
20 mm
Question Number: 117 Question Id: 47720321149 Display Question Number: Yes Is Question Mandatory: No  Which of the following defect is related to welding processes?
Options :
Mismatch  1. *
2. * Cold shut
Misrun 3. **
4. ✓ Undercut

Question Number: 118 Question Id: 47720321150 Display Question Number: Yes Is Question

Question Number: 116 Question Id: 47720321148 Display Question Number: Yes Is Question

The hot working process is generally carried out at a temperature	
Options :	
Greater than room temperature  1. **	
2.  ✓ Greater than recrystallization temperature	
Less than recrystallization temperature  3. **	
Greater than melting point 4. **	
Question Number: 119 Question Id: 47720321151 Display Question Number  Mandatory: No  allowance is provided on the pattern for easy removal without destroying the vertical walls of mould from the mould  Options:	oer : Yes Is Questioi
Options : Shake 1. **	
2. * Shrinkage	
3. ✓ Draft	
A. ** Ramming	
	collegedunia

Question Number: 120 Question Id: 47720321152 Display Question Number: Yes Is Question

Mandatory : No

# Mandatory: No Which of the following is not a defect of casting process? **Options:** 1. \* Blow holes Incomplete fusion Pin holes Shrinkage cavity Question Number: 121 Question Id: 47720321153 Display Question Number: Yes Is Question Mandatory: No Which of the following properties does a moulding sand should have to pass the hot gasses/vapour from the mould after pouring or during pouring? Options: Collapsibility Refractoriness

collegedunia

Cohesiveness

4. ✓ Permeability

Mandatory : No	r : Yes Is Question
If the maximum size of shaft is greater than the maximum size of hole, then the possible fit is	
Options :	
1. * Clearance fit	
2. ✓ Interference fit	
Transition fit	
Slide fit	
Question Number : 123 Question Id : 47720321155 Display Question Numbe Mandatory : No	r : Yes Is Question
In a bilateral tolerance system, the tolerance is provided on	
Options:	
One side of actual size	
One side of nominal size  2. **	
Both sides of actual size	
Both sides of nominal size	
<del>4</del> . ▼	collegedunia India's largest Student Review Platform

١.

Question Number : 124 Question Id : 47720321156 Display Question Number : Yes Is Question Mandatory : No

How many number of tolerance grades are available according to Indian standards?

#### **Options:**

- 1. \* 25
- 2. 🗸 18
- 3. \* 8
- 4. \* 12

Question Number : 125 Question Id : 47720321157 Display Question Number : Yes Is Question Mandatory : No

In a bilateral tolerance system, the shaft is specified as  $25^{+0.05}_{-0.02}$  mm. The tolerance provided on the shaft is \_\_\_\_\_

- 0.05 mm
- 0.02 mm
- 0.03 mm
- 0.07 mm



mandatory : No
The average surface roughness of a component is 6.3 µm. The ISO surface roughness grade is
Options:
1. ✓ N9
2. * N12
3. <b>*</b>
4. * N1
Question Number: 127 Question Id: 47720321159 Display Question Number: Yes Is Question Mandatory: No  In conventional drawing, the line drawn by repeating a long section followed by shot dash again long section represents
Options:
Hidden features  1. **
2. ** Radius of a circle
Central axis a cylinder 3. ✓
4. * Centre of a circle
collogodunia

#### Mandatory: No

An unknown material can be specified as a brittle material if its percentage of elongation is in uniaxial tensile testing

#### Options:

Question Number : 129 Question Id : 47720321161 Display Question Number : Yes Is Question Mandatory : No

Cast iron is a\_\_\_\_\_

# Question Number: 130 Question Id: 47720321162 Display Question Number: Yes Is Question Mandatory: No Which of the following testing comes under the category of non-destructive testing method? **Options:** Uniaxial tensile test Izod impact test Dye penetrate test 4. \* Bending test Question Number: 131 Question Id: 47720321163 Display Question Number: Yes Is Question Mandatory: No In iron and iron carbide diagram, the maximum percentage of carbon is **Options:** 1. \* 1.7 % 2. 4 6.67 % 3. \* 4.3 %

collegedunia

4. \* 0.8 %

Mandatory: No	. res is question
What is the percentage of carbon in mild steel?	
Options:	
1. ✓ Less than 0.5 %	
Between 0.5 % and 3 % 2. **	
3. * Between 3 % and 6.67 %	
More than 6.67 % 4. ■	
Question Number : 133 Question Id : 47720321165 Display Question Number	: Yes Is Question
Question Number : 133 Question Id : 47720321165 Display Question Number Mandatory : No	: Yes Is Question
	: Yes Is Question
Mandatory: No  Which of the following is a non-ferrous alloy?  Options:	: Yes Is Question
Mandatory: No  Which of the following is a non-ferrous alloy?	: Yes Is Question
Mandatory: No  Which of the following is a non-ferrous alloy?  Options:	: Yes Is Question
Mandatory: No  Which of the following is a non-ferrous alloy?  Options:  1. ✓ Brass  Mild steel	: Yes Is Question
Mandatory: No  Which of the following is a non-ferrous alloy?  Options:  1. ✓ Brass  Mild steel  Cast iron	: Yes Is Question  collegedunia

Question Number : 134 Question Id : 47720321166 Display Question Number : Yes Is Question
Mandatory : No
If two forces are said to be collinear, then
Options:
The line of action of the two forces is same  1. ✓
The line of action of the two forces is perpendicular 2. **
The line of action of the two forces is at obtuse angle
The line of action of the two forces is at an acute angle 4. **
Question Number : 135 Question Id : 47720321167 Display Question Number : Yes Is Question Mandatory : No
Two forces with same magnitude (100 N) but opposite in direction are acting on a body. If the line of action
of these forces is same, then the net resultant force magnitude acting on the body is
Options:
1. * 100 N
2. <b>×</b> 200 N
3. * 50 N
Zero  4. ✓

Question Number : 136 Question Id : 47720321168 Display Question Number : Yes Is Question Mandatory : No
Up to which point on stress strain curve, the Hooke's law is valid?
Options :
Ultimate tensile strength point  1. **
2. ✓ Proportionality limit
Lower yield point  3. **
Fracture point 4. **
Question Number : 137 Question Id : 47720321169 Display Question Number : Yes Is Question Mandatory : No
The ability of the material that absorbs energy till its fracture is known as
Options:  Brittleness  1. **
Ductileness 2. **
Toughness 3. ✓ collegedunia India's Largest Student Review Platform
4. * Malleability

Question Number: 138 Question Id: 47720321170 Display Question Number: Yes Is Question
Mandatory : No
If a simply supported beam is loaded with point load at its midpoint of the beam, then the deflection is maximum at its
Options :
Hinged supported end  1. **
Roller supported end 2. **
Both at roller and hinged supports  3. **
Midpoint of the beam 4. ✓
Question Number : 139 Question Id : 47720321171 Display Question Number : Yes Is Question Mandatory : No
If a cantilever beam is subjected to a point load at its free end, the shear stresses in the beam is
Options:
1. * Increasing gradually
2. * Decreasing gradually
3. Constant collegedunia

4. Zero

Question Number : 140 Question Id : 47720321172 Display Question Number : Yes Is Question Mandatory : No
The stresses produced in belt drive are
Options:  Tensile stresses  1.   Tensile stresses
1. Compressive stresses 2. Compressive stresses
Shear stresses 3. **
Both compressive and shear stresses  4. **
Question Number : 141 Question Id : 47720321173 Display Question Number : Yes Is Question Mandatory : No
Which of the following is a positive drive?
Options:
1. * Rope drive
Chain drive 2. ✓
Flat belt drive  3. **  Collegedunia India's largest Student Review Platform
4. * V-belt drive

# Question Number : 142 Question Id : 47720321174 Display Question Number : Yes Is Question Mandatory : No

A helical spring with stiffness of 100 N/m is cut into two parts. What is the stiffness of each part of the cut spring?

#### Options:

- 1. \* 25 N/m
- 100 N/m
- 3. **✓** 200 N/m
- 50 N/m

# Question Number : 143 Question Id : 47720321175 Display Question Number : Yes Is Question Mandatory : No

Let P is the tension in the flat belt due to centrifugal force. To achieve maximum power transmission with the flat belt drive, the maximum tension in the belt should be \_\_\_\_\_

- 1. 🗸 3P
- 2. \* P
- 0.333P



4. * 2P	
Question Number : 144 Question Id : 47720321176 Display Question Nu	mber : Yes Is Questior
Mandatory : No	
A flange coupling is used for	
Options:	
Intersecting shafts  1. **	
Collinear shafts 2. ✓	
Small shafts rotating at slow speeds  3. **	
4. * Parallel shafts	
Question Number : 145 Question Id : 47720321177 Display Question Nu	mber : Yes Is Question
Mandatory : No	
A key in the shape of semi-circular disk with uniform thickness is called as	
Options:	
1. * Sunk key	
Feather key 2. **	
3.  ✓ Woodruff key	collegedunia India's Largest Student Review Platform

4. •
Question Number : 146 Question Id : 47720321178 Display Question Number : Yes Is Question Mandatory : No
The function of fly wheel is to
Options:
Limit the fluctuations of speed during each cycle  1. ✓
Control the means speed of the engine 2. **
Maintain constant speed  3. **
Come into action when the speed varies due to varying load.  4. **
Question Number: 147 Question Id: 47720321179 Display Question Number: Yes Is Question Mandatory: No Which of the following threads are used for screw jacks?
Options :
Trapezoidal threads  1. **
2. * V threads
Buttress threads  Buttress threads

Kennedy key

Square threads 4. ✓
Question Number : 148 Question Id : 47720321180 Display Question Number : Yes Is Questio Mandatory : No
The specification of a thread is given as M 20 $\times$ 2. Which of the following is true?
Options :
It is a metric thread of 20 mm major diameter with 2 cm pitch  1. **
It is a metric thread of 20 mm pitch diameter with 2 cm pitch 2. **
It is a metric thread of 20 mm pitch diameter with 2 mm pitch 3. ✓
It is a metric thread of 20 mm major diameter with 2 mm pitch 4. *
Question Number: 149 Question Id: 47720321181 Display Question Number: Yes Is Questio  Mandatory: No  The thickness of the gear tooth is measured along the
Options:  1.   Pitch circle
Base circle  Collegedunia India's largest Student Review Platform  Addendum circle
<del>-</del> ·

Root circle 4. **	
Question Number : 150 Question Id : 47720321182 Display Question Number : Mandatory : No  The size of the gear is specified by	Yes Is Question
Options:  Circular pitch  1. **	
Diametral pitch 2. **	
Pitch circle diameter  3. **	
Module.  4. ✓ Module.	
Question Number : 151 Question Id : 47720321183 Display Question Number : Mandatory : No	Yes Is Question
The value of universal gas constant is	
Options:  80.314 J/kgK  1. **	
2. <b>*</b> 830.14 J/kgK	
28.7 J/kgK	collegedunia [sometimes in India's Largest Student Review Platform

Question Number : 152 Question Id : 47720321184 Display Question Number : Yes Is Question Mandatory : No

Which of the following is true?

#### **Options:**

Atmospheric pressure = gauge pressure + absolute pressure

1. \*\*

Absolute pressure = gauge pressure + atmospheric pressure

Gauge pressure = atmospheric pressure + absolute pressure

Absolute pressure = gauge pressure – atmospheric pressure

Question Number : 153 Question Id : 47720321185 Display Question Number : Yes Is Question Mandatory : No

The absolute zero temperature is taken as

4. **≈** −273 F

Question Number : 154 Question Id : 47720321186 Display Question Number : Yes Is Question Mandatory : No

Which of the following cycles consists of one constant pressure, one constant volume and two isentropic processes?

#### **Options:**

Otto cycle

1. \*\*

Carnot cycle

Diesel cycle

Stirling cycle

Question Number : 155 Question Id : 47720321187 Display Question Number : Yes Is Question Mandatory : No

Which of the following represent a first law of thermodynamics?

#### Options:

Conservation of momentum

Conservation of heat



Conservation of mass

Conservation of energy 4. ✓
Question Number : 156 Question Id : 47720321188 Display Question Number : Yes Is Question Mandatory : No
Which of the following liquid is most volatile and lighter in weight?
Options:  1. **
2. * Kerosene
3. ✓ Petrol
4. * Mineral oil
Question Number : 157 Question Id : 47720321189 Display Question Number : Yes Is Question  Mandatory : No  Work done in a free expansion process is
Options: Positive 1. **
2. Zero  Zero  indix's largest Student Review Platform
Maximum 3. **

Minimum 4. **	
Question Number : 158 Question Id : 47720321190 Display Question Numb Mandatory : No	er : Yes Is Question
The change in entropy of an irreversible process is always	
Options :	
1. ✓ Positive	
2. * Negative	
Remains constant 3. **	
4. * Zero	
Question Number : 159 Question Id : 47720321191 Display Question Numb Mandatory : No	er : Yes Is Questior
According to Avogadro's law, at same pressure and temperature, the density of two gases is their molecular masses.	
Options:	
1. * Equal to	
Directly proportional to 2. ✓	
Indirectly proportional to	collegedunia

Question Number : 160 Question Id : 47720321192 D	isplay Question Numbe	r : Yes Is Question
Mandatory : No		
The efficiency of Carnot cycle depends only on		
Options :		
1. * Pressure ratio		
Cut-off ratio		
Temperature limits 3. ✓		
Compression ratio 4. **		
Question Number : 161 Question Id : 47720321193 D Mandatory : No	isplay Question Numbe	r : Yes Is Question
For the same compression ratio, the efficiency of Otto cycle is	the diesel cycle.	
Options:  1.   Greater than		
2. * Less than		
3. * Equal to		
		collegedunia


Density does not depend on molecular mass

4. * Half
Question Number : 162 Question Id : 47720321194 Display Question Number : Yes Is Question Mandatory : No
The capacity of the compressor is generally expressed in
Options:  1. * kg/m <sup>3</sup>
2. * m <sup>3</sup> /kg
3. <b>*</b> kg/m <sup>2</sup>
4. ✓ m <sup>3</sup> /min
Question Number : 163 Question Id : 47720321195 Display Question Number : Yes Is Question Mandatory : No
The dynamic/absolute viscosity is the
Options:  Ratio of kinematic viscosity to the density of the liquid  1. **
Ratio of density of the liquid to the kinematic viscosity 2. **
Product of kinematic viscosity and density of the liquid  3. ✓

Question Number : 164 Question Id : 47720321196 Display Question Number : Yes Is Question Mandatory : No
The number of blades for a Kaplan turbine runner is generally varies from
Options :
1. * 16 to 24
2. <b>8</b> to 16
3. <b>*</b> 2 to 4
4. ✓ 4 to 8
Question Number : 165 Question Id : 47720321197 Display Question Number : Yes Is Question Mandatory : No
Discharge of a centrifugal pump is of the impeller
Options:
Directly proportional to the (diameter) <sup>2</sup> 1. ✓
Inversely proportional to the diameter 2. **
Directly proportional to the diameter

Product of kinematic viscosity and mass of the liquid

4. 💥



More than 1000 m Question Number: 168 Question Id: 47720321200 Display Question Number: Yes Is Question Mandatory: No At a constant head and discharge, what should be the speed ratio for a Pelton wheel to get maximum efficiency? **Options:** 0.35 1. \*\* 0.56 0.45 4. \* 0.26 Question Number: 169 Question Id: 47720321201 Display Question Number: Yes Is Question Mandatory: No To achieve higher hydraulic efficiency of an impulse turbine, the velocity of the wheel should be \_\_\_\_\_\_ of the jet velocity **Options:** One-half Three-fourth

3. \* Double

4. * One-fourth
Question Number : 170 Question Id : 47720321202 Display Question Number : Yes Is Question
Mandatory : No
If H is the head of water, then the discharge through turbine ( Pelton wheel) is
Options :
Inversely proportional to H <sup>3/2</sup>
2. * Inversely proportional to H <sup>1/2</sup>
Directly proportional to H <sup>3/2</sup>
4. ✓ Directly proportional to H <sup>1/2</sup>
Question Number : 171 Question Id : 47720321203 Display Question Number : Yes Is Question
Mandatory : No
The total energy line lies over the centre line of the pipe by an amount equal to
Options:
Velocity head  1. **
2. ** Pressure head
3. ✓ Velocity + pressure head

4. \* Pressure – velocity head

Question Number : 172 Question Id : 47720321204 Display Question Number : Yes Is Question Mandatory : No

The dryness fraction (x) of a super-heated steam is \_\_\_\_\_

### Options:

$$1. \times X = 0.5$$

$$x = 0.9$$

$$4. \checkmark x = 1$$

Question Number : 173 Question Id : 47720321205 Display Question Number : Yes Is Question Mandatory : No

At a constant pressure, the temperature at which the pure liquid phase transforms into vapour phase is known as \_\_\_\_\_

#### Options:

Normal temperature

Saturated temperature 2. ✔

Evaporative temperature

3. 💥



-		4	9.5	
Detti :	noint	tem	nerati	11'0
Dew	DOME	CLIII	Derait	110

Question Number: 174 Question Id: 47720321206 Display Question Number: Yes Is Question
Mandatory : No
In which of the following devices, the flow is generally considered as adiabatic?
Options :
1. ✓ Nozzle
2. ** Evaporator
Condenser 3. **
4. * Chimney
Question Number : 175 Question Id : 47720321207 Display Question Number : Yes Is Question
Mandatory : No
The function of a steam nozzle is to convert
Options :
Heat energy of the steam to potential energy
Heat energy of the steam to kinetic energy 2. ✔
Thermal energy of the steam to potential energy

Question Number : 176 Question Id : 47720321208 Display Question Number : Yes Is Question Mandatory : No
The ratio of actual enthalpy drop to the isentropic enthalpy drop is known as
・ 日本的になった。日本的になった。日本的にはないでは、日本のは、日本のは、日本のは、日本のは、日本のは、日本のは、日本のは、日本の
Options:
1. ** Stage efficiency
Coulomb efficiency
2. *
3. * Rankine efficiency
Internal/nozzle efficiency
4. 🗸
Question Number: 177 Question Id: 47720321209 Display Question Number: Yes Is Question
Mandatory : No
The axial thrust in a reaction turbine is because of across the rotor
Options:
1. Pressure and axial velocity drop
Pressure and temperature drop
2. **
T
Temperature and axial velocity drop  3. *
collegedunia India's largest Student Review Platform

Heat energy of the steam to thermal energy

4. * Pressure drop only
Question Number : 178 Question Id : 47720321210 Display Question Number : Yes Is Question
Mandatory : No
If a nozzle cross-sectional area is continuously decreasing from entrance till certain area and then
continuously increases till the exit is known as
Options:
1. * Convergent nozzle
Divergent nozzle 2. **
Convergent-divergent nozzle 3. ✔
Divergent-convergent nozzle 4. **
Question Number : 179 Question Id : 47720321211 Display Question Number : Yes Is Question
Mandatory: No
The function of governing system in steam turbines is to
Options:
Control the dryness ratio  1. **
2. ✓ Maintain the speed of turbine
Maintain required torque  3. **

4. * Monitor the axial thrust of the turbine
Question Number : 180 Question Id : 47720321212 Display Question Number : Yes Is Questio Mandatory : No
Expansion process in refrigeration cycle is an
Options:
1. * Isentropic
2. ✓ Isenthalpic
3. * Isothermal
4. * Isobaric
Question Number : 181 Question Id : 47720321213 Display Question Number : Yes Is Questio Mandatory : No
The condenser and evaporator in vapour compression refrigeration cycles operates at constant
Options :
Volume  1. **
Temperature 2. **
3. Pressure
collegedunia India's Largest Student Review Platform

### Entropy

## Question Number : 182 Question Id : 47720321214 Display Question Number : Yes Is Question Mandatory : No

If the coefficient of performance (COP) of a heat pump is 5.0, then what would be the coefficient of performance of a refrigerator operating at the same temperatures as the heat pump?

#### **Options:**

- 1. \* 3.0
- 2. 🗸 4.0
- 3. \* 6.0
- 4. \* 5.0

# Question Number : 183 Question Id : 47720321215 Display Question Number : Yes Is Question Mandatory : No

The capacity of refrigeration is generally expressed in tonnes. One tonne is equal to amount of heat removal?

- 1. \* 420 kJ/min
- 2. \* 105 kJ/min
- 3. **≈** 200 kJ/min



		210	kJ/	min
4.	$\checkmark$	omanue o	-	

Question Number : 184 Question Id : 47720321216 Display Question Number : Yes Is Questior
Mandatory : No

In inventory control, the term economic order quantity (EOQ) means

#### **Options:**

- 1. ✓ Optimum lot size
- Maximum size of warehouse needed
- Maximum lot size to be ordered
- Lot size resulted from break-even analysis

Question Number : 185 Question Id : 47720321217 Display Question Number : Yes Is Question Mandatory : No

Which type of the following organisation is preferred for steel industry?

- Functional organisation
- Line and staff organisation
- Line, staff and functional organisation



Question Number : 186 Question Id : 47720321218 Display Question Number : Yes Is Question Mandatory : No
A diagram that shows the path to be followed by a working staff or materials while performing a task is known as
Options:
1. ** Travel chart
Flow process chart
3. * String diagram
Flow diagram 4. ✓
Question Number : 187 Question Id : 47720321219 Display Question Number : Yes Is Question
Mandatory : No The work study involves
Options:
Method study and Motion study.
2. * Work measurement
3. ✓ Both method study and work measurement
collegedunia India's largest Student Review Platform

Line organisation only

4. \*\*

Question Number : 188 Question Id : 47720321220 Display Question Number : Yes Is Question
Mandatory : No
ABC analysis is generally used in
Options:  1. * PERT
2. ✓ Inventory control
3. <b>*</b> CPM
Break-even analysis 4. **
Question Number : 189 Question Id : 47720321221 Display Question Number : Yes Is Question Mandatory : No
The total cost in a break-even analysis is a sum of
Options:
Fixed cost and revenue  1. **
Fixed cost and profit 2. **
Variable cost and revenue  3. **

collegedunia 
India's largest Student Review Platform

4. ❖
Question Number: 190 Question Id: 47720321222 Display Question Number: Yes Is Questio  Mandatory: No  To manufacture steam turbines, which of the following layout is most appropriate?
Options:
Process layout  1. **
2. * Product layout
Fixed position layout 3. ✓
Either process or product layout  4. **
Question Number : 191 Question Id : 47720321223 Display Question Number : Yes Is Questio
Mandatory : No
The full form of PERT is
Options :
Planning Estimation and Resulting Technique  1. **
Programme Evaluation and Review Technique
Programme Evolution and Resulting Technique  3. **  Collegedunia: India Largest Student Review Platform

Fixed cost and variable cost

Question Number : 192 Question Id : 47720321224 Display Question Number : Yes Is Question Mandatory : No
In manufacturing management, the term "dispatching" refers to
Options :
Dispatching of work orders through shop floor  1. ✓
Dispatching factory mail
3. * Dispatching of sales order
Dispatching of finished product of the user
Question Number : 193 Question Id : 47720321225 Display Question Number : Yes Is Question
Mandatory : No
Scheduling is
Options:  Concerned with starting of the process
Prescribes the sequence of operations to be followed  2. **
Determines the programme for the operations  3.   collegedunia
India's largest Student Review Platform

Process Estimation and Resulting Technique

Regulates the progress of the jobs 4. **	
Question Number : 194 Question Id : 47720321226 Display Question Number : Yes Is Que	stion
Mandatory : No	
Which of the following is used to transfer the motion from cam to valves?	
Options:	
Rocker arms 1. ✓	
Camshaft 2. **	
3. * Connecting rod	
4. * Chain drive	
Question Number : 195 Question Id : 47720321227 Display Question Number : Yes Is Que	estior
Mandatory : No	
The piston and connecting rod in an automobile engine are generally connected by	
Options:	
Kingpin  1. **	
2.  ✓ Gudgeon pin	
Stud  3. ** collegedu	ınia:
India's largest Student Revic	ew Platform

Rivet 4. **	
Question Number: 196 Question Id: 47720321228 Display Question Number: Yes Is Question	n
Mandatory : No	
In the contest of automobile industry, the full form of ABS is	
Options:	
Antirust Braking System  1. **	
Automatic Braking System  2. **	
Auto-lock Braking System 3. **	
Anti-lock Braking System 4. ✔	
Question Number: 197 Question Id: 47720321229 Display Question Number: Yes Is Question Mandatory: No  Which of the following is not a part of transmission system of an automobile?	n
Options:	
Differential  1. **	
2. ✓ Engine	
Propeller shaft	

Gear box
Question Number : 198 Question Id : 47720321230 Display Question Number : Yes Is Question
Mandatory : No
The cross-section of connecting rod resembles shape.
Options:
1. * H
2. <b>*</b>
3. <b>V</b>
4. * C
Question Number : 199 Question Id : 47720321231 Display Question Number : Yes Is Question
Mandatory : No
The purpose of differential in the automobile transmission system is to
Options:
Have same speed to the front wheels  1. **
Have different speeds to the rear wheels  2.
Have same speed to the rear wheels

Question Number: 200 Question Id: 47720321232 Display Question Number: Yes Is Question

Mandatory : No

Which of the following is not a part of chassis assembly?

- 1. Front axle
- 2. Wheels
- 3. \* Engine
- 4. Rear seats

